

BILANS ROBÓT ZIEMNYCH – ul. Bukowa							
Pikietą	Pow. wykopu	Pow. nasypu	Obj. wykopu	Obj. nasypu	Całk. obj. wykopu	Całk. obj. nasypu	Obj. netto
0+010.3	3.1	0.0	0.0	0.00	0.00	0.00	0.00
0+012.9	3.2	0.0	8.0	0.00	8.02	0.00	8.02
0+026.4	2.7	0.0	39.9	0.00	47.88	0.00	47.88
0+044.1	1.7	0.1	38.9	0.60	86.75	0.60	86.14
0+062.3	2.2	0.2	35.5	2.43	122.27	3.03	119.24
0+090.4	2.6	0.1	67.6	3.70	189.83	6.73	183.09
0+108.8	3.4	0.0	54.9	0.63	244.78	7.36	237.41
0+123.5	3.2	0.0	48.3	0.04	293.11	7.40	285.71
0+140.7	3.6	0.0	58.4	0.02	351.51	7.41	344.09
0+167.0	3.0	0.0	86.8	0.06	438.32	7.47	430.85
0+188.5	3.8	0.0	73.6	0.05	511.90	7.52	504.38
0+214.4	3.5	0.0	94.4	0.00	606.29	7.52	598.77
0+236.5	3.0	0.0	71.9	0.03	678.23	7.55	670.68
0+255.2	2.8	0.0	54.6	0.26	732.81	7.81	725.01
0+274.6	3.6	0.0	62.2	0.24	795.04	8.05	787.00
0+292.3	3.3	0.0	61.0	0.00	856.08	8.05	848.03

Tab. 1 Tabela robót ziemnych